



Example wraps of VRV IV+ condenser and Sky Air condenser

Daikin inhouse customised wrapping service for condensers and indoor units.

A customised service to ensure that your units are as discrete as possible so any disturbance to the neighbours is minimised. During the planning submission process efforts to minimise the visual impact of condensers is always appreciated. This service allows a unit to be merged with its background by creating a wrap that is matched as closely as possible, using a high quality photograph.

Service offer

- › Customised unit wrapping service of outdoor and indoor units
- › Service carried out by Daikin inhouse for high quality
- › Wrap matched to the background of your choice
- › Enables units to be blended with its surroundings

Daikin Inhouse service to ensure quality

Daikin will carry out all aspects of the service in house to ensure that the wrap is added with the highest quality standards in mind. Each panel is removed, wrapped and carefully replaced. It is delivered to site with the required protective packaging. The Daikin warranty covers the wrap process.

Specification

Based on a customer photograph, a high quality printed vinyl wrap with laminate cover will be carefully applied to the customer's unit. The wrap is a high quality vinyl; 50 micron Cylinder Cast digital wrapping media. The soft film has been developed to flow and conform over the most challenging surfaces so it's ideal for total condenser wraps.

Over lamination prevents abrasion, extends colour fastness and also offers easier handling. Safety badges and specification plate will be carefully removed and reapplied where applicable or wrapped around.



Daikin Unit Wrapping Service

Additional considerations

The plastic grille is not wrapped but painted in a similar colour for the closest match. Outdoor unit brackets and associated pipe trunking can be colour matched to suit (not wrapped).



Operational and Install considerations

- Service temperature -30°C to +110 °C
- Fire rating - self-extinguishing
- During install it is recommended to place a wet-rag on the condenser side, where the brazing is carried out to protect the wrap from excessive heat.
- No issues with servicing – this can be carried out as normal
- The chemical resistance unprinted film is resistant to mild acids, aliphatic solvents, salt and alkali, diesel, oil, gasoline, paraffin, hydraulic oil and antifreeze.

The present leaflet is drawn up by way of information only and does not constitute an offer binding upon Daikin UK. Daikin UK has compiled the content of this leaflet to the best of its knowledge. No express or implied warranty is given for the completeness, accuracy, reliability or fitness for particular purpose of its content and the products and services presented therein. Specifications are subject to change without prior notice. Daikin UK explicitly rejects any liability for any direct or indirect damage, in the broadest sense, arising from or related to the use and/or interpretation of this leaflet. All content is copyrighted by Daikin UK.

Match the surrounding

It is important to take a good quality photograph and to send it through to your local Daikin sales office. Also, consider the time of day and weather conditions; whether it is wet or dry. Sunny or cloudy can also have an impact on the photograph so consider what you require. Daikin will prepare a sample from your photograph and send back to you for approval. The photograph should be a high-definition 300ppi (pixels per inch). If taking a suitable photograph is challenging then many high definition images can be found on websites such as shutterstock www.shutterstock.com.

Process

- › Order wrap based on unit size – see price table
- › Select unit location
- › Photograph backdrop against which the unit is to be placed
- › Send high resolution image to Daikin sales office
- › Daikin will create a vinyl to match and send it back to you for approval
- › Following your approval the wrapping process will commence
- › Delivery is 2-3 weeks following approval of the wrap sample.

Attention to detail during wrapping process

During the wrapping process each panel is carefully removed, primed and wrapped, then replaced with washers to ensure the wrap integrity.

